2015

Putnam County Townships Road Improvement Project

BID TABULATION

Bid Opening: June 25, 2015

Bidding Contractor: **Ward Construction**

Plans Received: 6/16/2015

Bid Item	Item Description	Est. Quanity	Units	Unit Price Material	Unit Price Labor	Estimated Unit Price	Total Price
203	Roadway Excavation	0	CY	$ -	$ 26.00	$ 26.00	$ -
204	Subgrade Compaction	0	SY	$ -	$ 1.00	$ 1.00	$ -
250	Full Depth Base & Pavement Spot Repairs	222	SY	$ 23.00	$ 27.00	$ 50.00	$ 11,100.00
254	Pavement Planning	10349	SY	$ -	$ 2.00	$ 2.00	$ 20,698.00
301	Asphalt Concrete - Base Course	0	Ton	$ 56.00	$ 29.00	$ 85.00	$ -
304	Aggregate Base	0	Ton	$ 10.00	$ 16.00	$ 26.00	$ -
405	Asphalt Concrete - Cold Mix - CM 90	1053	Ton	$ 64.00	$ 19.00	$ 83.00	$ 87,399.00
405	#9 Stone Choke for Cold Mix	76	Ton	$ 15.00	$ 15.00	$ 30.00	$ 2,280.00
448	Asphalt Concrete Inter. - Hot Mix 64-22	998	Ton	$ 57.00	$ 15.00	$ 72.00	$ 71,856.00
448	Asphalt Concrete Surface - Hot Mix 64-22	4774	Ton	$ 57.00	$ 15.00	$ 72.00	$ 343,728.00
448	Asphalt Concrete Leveling - Hot Mix 64-22	40	Ton	$ 57.00	$ 43.00	$ 100.00	$ 4,000.00
408	Prime Coat (0.35 gal/SY)	0	Gal	$ 2.25	$ 1.25	$ 3.50	$ -
409	Tack Coat (SS-1 0.10 gal/SY)	3225	Gal	$ 2.00	$ 0.30	$ 2.30	$ 7,417.50
411	Stabilized Crushed Aggregate	887	Ton	$ 9.00	$ 6.00	$ 15.00	$ 13,305.00
422	Chip Seal Asphalt Emulsion - HFRS-2P	98446	Gal	$ 2.15	$ 0.50	$ 2.65	$ 260,881.90
422	Chip Seal Aggregate Cover # 8 Stone	2039	Ton	$ 11.00	$ 14.00	$ 25.00	$ 50,975.00
422	Chip Seal Aggregate Cover # 9 Stone	936	Ton	$ 13.00	$ 14.00	$ 27.00	$ 25,272.00
624	Mobilization	15	Ea.	$ -	$ 500.00	$ 500.00	$ 7,500.00
614	Maintaining Traffic	15	Ea.	$ 50.00	$ 250.00	$ 300.00	$ 4,500.00

TOTAL $ 910,912.40